

## ADDENDUM

### **SUPPLY & INSTALLATION OF 200 KW GRID-TIED SOLAR POWER SYSTEM WITH DB PANEL, PARKING SHED STRUCTURE & REQUISITE CABLING WORKS ETC. AT G5 NBP-ISLAMABAD**

A subject tender **NT-01/16/2025-1** has been posted at NBP as well as PPRA websites on 16/01/2025 and queries being raised by the bidders, following amendment/revision was made in bidding document:

- Inverter brands mentioned in form 5 of Section VI (Standard Forms of Bid) on Page No: 64 of the bidding document is amended as under:  
**GROWATT, SUNGROW, SMA & Huawei or Equivalent.**
- Maximum input voltages of inverter in sub-section B (Technical specifications) of sections V (Schedule of Requirements, Technical Specifications) on Page No: 52 of bidding document is amended as under:  
**Maximum Input voltage: 1100v**
- MPPT Operating Voltage Range of inverter in sub-section B (Technical specifications) of sections V (Schedule of Requirements, Technical Specifications) on Page No: 52 of bidding document is amended as under:  
**MPPT voltage range: 180 to 1000v Dc.**
- Certifications/standards conformance in sub-section B (Technical specifications) of sections V (Schedule of Requirements, Technical Specifications) on Page No: 53 of bidding document is amended as under:  
**IEC 62109-1 (Safety and Performance)**  
**IEC 62920 (EMC)**

All other terms, conditions and requirements remain the same.

Thank You



---

**Zubair Ali Malik**  
**Wing Head, Engineering South**

